

**Smoke Duct Slab Erection Gantry and Corbel Anchor Drilling System Design  
for the Transcity JV, Legacy Way Road Tunnel Project, Brisbane**

Simon Strong, BEng (Mech) Hons

Herrenknecht Australia

**Submitted to**

**The Australasian Tunnelling Society (ATS)**

**for**

**The David Sugden Young Engineers Writing Award, 2014**

## 1. Abstract

This paper aims to describe the design of two purpose-built machines assisting the construction of a smoke duct in the Legacy Way tunnel project. The innovative civil design of the smoke duct required an equally innovative solution for its construction. The engineering team responsible for delivering the prototype machines endeavoured to solve the problem with simple designs. This paper will provide a background for the project, describe the specific problem, and then discuss in detail the development of the design solutions and the challenges faced along the way. The performance of the final product is also evaluated from a machine design perspective.

## 2. Project Background

Legacy Way is a twin two-lane, 4.6 km road tunnel project in Brisbane, Australia. Transcity joint venture (TJV) is the principal contractor managing the design, construction and operation of the tunnel. Excavation of the 12.4 m diameter tunnels was completed in June 2013, with disassembly of the Herrenknecht tunnel boring machines (TBMs) and invert backfilling finalised soon thereafter. The next phase of construction was the installation of a smoke duct system as a part of the tunnel ventilation scheme. In two previous local projects an entirely cast in situ solution was adopted for the smoke duct construction. TJV however developed an innovative alternative using a cast in situ corbel to support precast concrete slab elements. The smoke duct itself is formed by the existing circular tunnel apex and the installed concrete ceiling, which is continuous along the entire tunnel length (refer Figure 1).

The following construction process was employed for the smoke duct system:

1. Scabbling of the concrete tunnel segments on each side of the tunnel wall where the corbel is to be formed
2. Drilling of anchor holes, and subsequent installation of chemically set rebars
3. Installation of a pre-fabricated reinforcement cage, tied to the rebars
4. Pouring of the concrete corbel from a formwork gantry, followed by a curing period
5. Erection of precast smoke duct slabs
6. Final works including sealing, drainage, painting and jet fan hanger installation




Figure 1 – Typical smoke duct cross section

Discussions for custom designed machines to drill the anchor holes and to erect the precast smoke duct slabs began in late 2012. A request for tender was received in December 2012 for a Smoke Duct Slab Erection System (SDSES) and in February 2013 for a Corbel Anchor Drilling System (CADS). The SDSES was awarded in February 2013 and the CADS in August 2013.

Having successfully tendered for the design and supply of the SDSES and CADS machines, Herrenknecht Australia set out to achieve an efficient and cost-effective solution with a focus on design simplicity and innovation. The following sections describe the development of these solutions and the final results are evaluated.

### **3. Herrenknecht Australia design team**

Herrenknecht is a world-leading supplier of mechanized tunnelling machines and associated equipment for all round tunnelling solutions. Herrenknecht Australia (HKAU), a subsidiary of the global organisation, comprises a small team offering site support to active local tunnelling projects before, during and after TBM excavation. In house engineering capabilities allow HKAU to work with tunnelling contractors to find solutions to unique and challenging problems related to tunnel construction.

Both the SDSES and CADS machines were to be prototype designs for HKAU. The design team responsible for delivering the SDSES and CADS to TJV included a project manager, mechanical engineer, an electrician/PLC specialist, and a mechanical draftsman. This small team managed the design of the prototypes while concurrently providing engineering assistance for the disassembly of the Legacy Way TBMs, amongst other activities.

## **4. Smoke Duct Slab Erection System**

### **4.1. Design brief**

The design brief for the SDSES was to supply a safe system for unloading, lifting and accurately placing the smoke duct slabs on top of the corbel. The pre-stressed, precast concrete smoke duct slabs were nominally 200 x 2000 x 8600 mm in size, with a mass of 8.6 T each, and a total quantity per tunnel of 2125. An independent machine was required in each tunnel. The slabs were to be constructed with integral lifting anchors on the top surface for connecting to proprietary, rated lifting clutches. The original brief identifies three types of slabs; a typical slab, a jet fan slab which would have hangers attached to the tunnel lining, and a damper panel slab, all three being equal in dimensions and weights.

The production objective was initially defined as 3 slabs to be installed per hour, later updated to 8 slabs per hour, with a minimum possible crew commencing production on 1 December 2013.

It was necessary to maintain a 4 m high x 3.5 m wide traffic clearance envelope through the machine for tunnel construction traffic and for the slab delivery vehicles. The SDSES would need to negotiate the 1500 m horizontal tunnel curve, and a  $\pm 5\%$  maximum tunnel grade.

Compliance with relevant Australian Standards was also a requirement, particularly with regard to the lifting devices, steel structures and electrical systems.

## 4.2. Design challenges

Elements of the original design specification were identified as particularly challenging. Slabs were to be delivered longways, lifted approximately 7 m by the SDSSES and once above corbel level, rotated 90 degrees. The SDSSES would then need to drive backwards to accurately place the slab ahead of its predecessor. The movement of the slab above the corbel was limited to a very small window, with clashing possible against the tunnel wall and against the top of the corbel. Design clearances were no greater than 100 mm for movement in any direction. A low point sump halfway along the tunnel alignment required the SDSSES to drive onto a 70 m long floor level raised 525 mm above the normal road height. The changing elevation of the road level translated to a changing installation height of the slabs, compounding the challenge of clash prevention. This section of the tunnel represented only 2% of the total tunnel length, but required careful consideration.

The load bearing capacity of the roadway was also identified as an area of design risk. It would be necessary to spread the SDSSES wheel loads out to prevent any damage to the permanent civil road works.

Further challenges were introduced after award of the supply contract. The different slab types changed in size and weight such that the maximum load increased to 10 T. This had implications for the stability of the structure and for the resultant wheel loads. Adding counterbalance to resolve the stability ultimately required additional load-balanced wheels to be installed.

The original delivery date was brought forward by 3 months to allow the SDSSES to be assembled and lifted into the tunnel portal earlier, optimizing crane operations on site. The shortening of the project timeline added pressure to the fabrication of the steel structures and the delivery of long lead-time items such as the extra wheel blocks required to distribute the ground bearing load.

## 4.3. Solution

The concept for the SDSSES was inspired by photographs found online by TJV. HKAU was able to track down the project in China and organise a trip to site which allowed HKAU and TJV representatives to witness the potential concept in action. Motivated by the possibility of such a system, and in accordance with TJVs design brief the agreed design of the SDSSES was a pair of independent, self-propelled, rolling gantries in a portal-type, rail-mounted configuration. A diesel generator provided power for all operating functions, which were controlled via a Siemens safety PLC.

Design simplicity was attempted by reducing the quantity of moving parts or mechanisms and by using componentry common to Herrenknecht's tunnelling equipment. Complexity was minimised by opting for a complete electric system. The functional components were limited to the longitudinal rail travel, lateral boom slew, hoist unit rotation and hoist raise/lower. Electric, braked gear motors were used for the wheel drives for the longitudinal travel, for the lateral slewing of the main boom structure, and for the hoist unit rotation. Variable frequency drives allowed for both rapid travel and fine adjustment, satisfying both the production cycle time and the required accurate slab placement. Electric chain hoists were used for the hoist raise/lower function.

The solution for clash prevention relied upon smooth and accurate operator control rather than sensors or devices. Based on previous experience, particularly while observing operators use the TBM tunnel segment erector device, it was considered more practical to use operator skill in favour of engineered limitations and constraints.

The low point sump height change was managed in the structural design without allowance for jacking of the portal structure or by any other method. This forced the design height of the hoist unit to be compressed since it needed to be low enough to avoid the tunnel apex while traversing the low point sump, but high enough to clear the slabs over the corbel while on normal road level.

The design of the different smoke duct slabs evolved in the early phase of the project. The mass of the slabs increased, and the structural design, machine stability and ground loading needed to be reanalysed. Counterweight in the SDSSES structure solved the stability, but the increased mass required that the wheel loads be spread out further on the rails. More wheel blocks were added, resulting in two-wheel assemblies at the front and three-wheel assemblies at the rear. The structure required no major additions besides the bogie assemblies, but the delivery of the additional wheel blocks became critical.



*Figure 2 – Inspiration from China*



Figure 3 - SDES basic elements

- |                           |                        |
|---------------------------|------------------------|
| 1. Hoist unit             | 6. Switchboard         |
| 2. Truss boom             | 7. Diesel generator    |
| 3. Boom slew wheel drive  | 8. Remote control unit |
| 4. Lifting beam           | 9. Rail wheel drive    |
| 5. Portal frame structure |                        |




Figure 4 – SDES GA elevation

Emergency stops were provided at key locations, including the remote control. Sensors were included for the longitudinal travel, with a set at each wheel assembly looking down to sense the end of the rail and one at each leg looking out along the rails for obstructions. Load cell pins were installed at each hoist to prevent overload. Certain functions were restricted by the PLC to prevent unsafe operation, including the tilting function which was limited to a small range of angular movement, and, when loaded, the hoist rotation function was limited to a small window near the top limits to prevent uncontrolled swinging and twisting in the chains.

<b>General Data</b>	
Description	Two independent, self-propelled, portal-type cranes on rails
Installed power	100 [kW]
Diesel generator	165 [KVA]
Control	PLC programmed functions, Hetric remote control operated
Mass (unloaded)	30 [T]
<b>Rail Wheel Drive</b>	
Rail material	A75 standard steel rail
Front wheels	Twin-wheel, load balanced bogie assembly, 1 x driven wheel per assembly
Rear wheels	Triple-wheel, load balanced bogie assembly, 1 x driven wheel per assembly
Wheel type	Flanged, spheroidal graphite cast iron
Max. single wheel load	47.6 [kN]
Wheel drive	Demag angular braked gear motor, 2.20 kW, 1:144 gear ratio, frequency converter controlled
Brake torque	17.0 [Nm]
Cooling	Forced air
Travel speed (fast/slow)	6.0/2.0 [m/min]
Sensors	3 x downward looking rail proximity sensors at each bogie assembly (slow, stop and failsafe) 1 x laser sensor at each gantry leg looking out along rail for obstructions
<b>Truss Boom</b>	
Cantilever	5.0 [m] rear of portal structure to centreline of hoist unit
Pivot joint	UHMWPE plain bearing pivot at front end of Truss Boom (non-lubricated)
Wheel type	Non-flanged, spheroidal graphite cast iron
Wheel arrangement	1 x driven + 1 x non-driven wheels
Wheel drive	Demag angular braked gear motor, 0.55 kW, 1:351 gear ratio, frequency converter controlled
Brake torque	2.5 [Nm]
Cooling	Forced air
Travel speed (fast/slow)	1.6/0.4 [m/min]
Travel range	±8° slew angle to provide ±1.8 [m] lateral adjustment
Sensors	2 x downward looking rail proximity sensors each side (slow, stop)
<b>Hoist Unit</b>	
Capacity	11.2 [T] SWL
Lifting Beam Rated Capacity	9.5 [T]

Lifting Beam Tare Mass	1.4 [T]
Overload prevention	4 x Load cell pins to detect 1-, 2- or 4- point hoist overload
Hoist	4 x 5.0 [T] Hadeff electric chain hoists
Hook stroke	9.0 [m] max.
Hoist travel speed (fast/slow)	4.0/1.0 [m/min]
Hoist power output	4.0/1.1 [kW]
Hoist operation	1-, 2- or 4-hoist simultaneous operation for raise/lower and level adjustment PLC controlled tilting limits to prevent overload/overbalance
Rotation description	Toothed slew ring bearing
Rotation drive	Demag angular braked gear motor, 0.55 kW, 1:120 gear ratio, frequency converter controlled
Brake torque	1.3 [Nm]
Cooling	Forced air
Rotation speed (fast/slow)	2.0/1.0 [rpm]
Rotation range	±90° nominal, mechanical end stops at ±100°
Rotation Sensors	2 x proximity sensors at 0°, +90° and -90° (slow, stop)

Table 1 - SDES technical specification

The critical path of the project was the engineering, procurement of long lead time items, fabrication and assembly. Early in the project the delivery date was brought forward by 3 months, and the revised schedule (see Figure 5) required that the critical path be further compressed and some critical activities needed to be done in parallel rather than in series. HKAU took some risk in ordering long lead time items, and ordering fabrication work before the final design was complete. The time allowed for workshop assembly and commissioning was also reduced.

The two SDES units were workshop commissioned in late September and delivered to site in mid-October. The plan for cranes changed and the machines sat idle of the surface until mid-November. An open-item list from the workshop commissioning required some additions and modifications and these were completed prior to assembly in the Western Portal shaft.





Figure 5 - SDES project schedule



#### 4.4. Operation, problems & solutions

Operation commenced in late December 2013. There were initially four people per crew per gantry, with two operators standing on top of the previously installed slab, and two operators at road level. A harness and tether system was used to prevent falls. Operator confidence quickly advanced as the production process was refined and perfected. The initial production objective was to complete up to 8 no. slabs per hour over a 12 hour shift, i.e. 96 slabs per shift at an average cycle time of 7.5 minutes. The progress of the SDSSES was limited by the formwork gantry ahead, and the concrete curing time. Subsequently the maximum number of slabs installed per shift was limited to approximately 48 (cycle time 15 minutes), at 3 slabs per trailer for a total of 16 deliveries per shift. The trucks were backed up and waiting in the tunnel, and it was recognised very early in the production phase that operating on night shift, and alternating between the east bound and west bound tunnels would adequately satisfy the production objectives while minimising disruption to other tunnel construction activities from the truck movements. The crew was reduced to a total of three people for the two gantries during a shift. The final slab was installed in May 2014, 5 months after start of production.

Prior to reaching the low point sump midway along the tunnel alignment it was realised that the ramp had a much steeper grade than expected, meaning the truss boom would clash with the tunnel segments. A solution was found to reduce the height of the gantry by replacing the wheel assemblies with a single wheel block at each leg of the gantry. A methodology was devised for the height change, and the production crew followed the procedure efficiently. The height change did not affect the operation of the hoist unit, so slab installation continued after the modification without interruption. After the low point sump the bogie assemblies were reinstated and production continued per normal.



*Figure 6 – Production phase (damper panel installation)*

Another problem encountered during operation was the impact of the load on the electric chain hoist top limit switches. The hoist raise speed was not reduced near the top of the stroke, and over time the switches became damaged and faulty. HKAU technicians modified the PLC program to step down the hoists to low speed mode near the top of the stroke, and the limit switches were replaced. After the modification no further problems were encountered.

TJV provided consistent and effective maintenance throughout the production phase in accordance with the HKAU operation manual. Operator training and site commissioning were provided by HKAU prior to start of operation, and technicians were available for site support throughout the project. There were no signs of fatigue in the structure, nor were there issues with the electrical system or diesel generator. The lifting beam hooks were monitored for wear, but the wear did not exceed allowable limits.

#### **4.5. Evaluation**

Overall the two prototype SDES machines satisfied TJV's design brief and performed at or above expectations. In terms of production objectives the system executed its task above requirements without unexpected downtime. The SDES was not on critical path for production which allowed TJV project managers some flexibility with resources, relieving pressure on other activities.

Mechanically the machine was mostly satisfactory, though the decision to keep the portal structure at a fixed height for all road levels was perhaps incorrect. Although the production objectives were not greatly impacted by the low point sump height change, had capability to jack the legs been provided it could be speculated that the operation would have been seamless. Besides the hoist limit switch issue, all moving parts worked flawlessly throughout the project. The structural design was without issue, and the assembly and disassembly procedures were effective.

From an electrical design perspective there were small adjustments made to the PLC to refine the operation, but ultimately the design was effective. The lighting, indication lamps, sensors and remote control all performed as required.

The shortened lead time added risk to the design, but the use of common components, a very simplified system, and a reasonably generous factor of safety on the structural design mitigated this risk through reliability and robustness. The lead time was mostly affected by the long lead time components and several fabrication issues which needed to be resolved during workshop assembly. Overall the project schedule was achieved without major delays.

To the authors knowledge there was no damage to the road structure from the wheel loads. Nor were there any segments damaged during installation from operator error or from normal operation of the machines.

The SDES system was an effective prototype, surpassing most expectations, and it is conceivable that a precedent has been set for similar systems to be used in future applications.

## **5. Corbel Anchor Drilling System**

### **5.1. Design brief**

The CADS design brief was to supply a semi-automated system for accurately drilling a prescribed radial pattern of holes in the tunnel segmental lining. The drilling pattern consisted of a quantity of 12, 25 mm diameter, 300 mm deep anchor holes on each side of the tunnel per 2 m wide tunnel ring, with a bottom and top row of 6 holes each. A total of approximately 51,000 holes were required per tunnel. An independent rolling gantry was to be provided by TJV for each tunnel, upon which the drilling system was to be installed. A variety of drilling patterns were initially specified, with accurate hole positions required to avoid the internal steel reinforcement. The range of hole positions required fine adjustment of the CADS vertically, longitudinally and angularly.

The drill position was to be firmly maintained during the drilling operation, and once the required hole depth was achieved, the drill was to be retracted automatically. The 300 mm drill depth needed to be accurately controlled. In the event of hitting reinforcement bar it was required that the drill stop and be manually retracted before causing damage to the drill bit.

The production objective was defined as 20 tunnel rings to be drilled per shift, or 480 holes, at an average of 1.5 minutes per hole. At this high rate of production it was determined that 8 independent drilling rigs would be required, 4 each side of the tunnel, with 2 to complete the top row and 2 to complete the bottom row of holes. A crew of 4 people per gantry was to commence production in late October 2013.

### **5.2. Design challenges**

Per the SDSSES the CADS was also required to operate within the tunnel construction tolerances, horizontal and vertical curves, and the low point sump height change. The gantry, supplied by UniSpan, also had its own inherent flexibility. Maintaining the tight tolerances on the hole positions and angles, coupled with the required production rate was the major design challenge for this project.

Development of a prototype system was a design challenge, and producing 16 independent drilling rigs within the project timeline and ready for production multiplied the magnitude of this challenge.

### **5.3. Solution**

The basic solution for the CADS was a set of 8 custom-designed, independent, semi-automatic drilling rigs per tunnel, mounted on a UniSpan portal-type, rail-mounted gantry structure (gantry supplied by TJV). Each rig was equipped with an electric Hilti percussive drill, and a Hilti dustless system incorporating a hollow drill bit and vacuum unit (supplied by TJV). Each drilling unit could be shifted manually and independently in the longitudinal direction along floor mounted rails, with the rail length allowing 4 tunnel segments to be drilled with each consecutive advance of the gantry. Height adjustment was provided in two ways. An innovative manual raising/lowering system was included to adjust the rig height only over the low point sump area. This system was designed as an inexpensive method which eliminated manual lifting. For regular operational height adjustment an electric ball screw linear actuator was provided to drive a parallel linkage mechanism. Angular

adjustment was made possible by a manual system. The drill rig feed rail could be extended and braced against the tunnel wall by actuation of a pneumatic cylinder. Similarly the drill stroke was actuated by a pneumatic cylinder. The drill cylinder had integral reed switches at each extent of the stroke to assist with the automation.

Given the various necessary functional movements of the rig and the accurate tolerances required, there was a risk that the system could suffer from over complication. TJV's preference was to use automated distance measuring to maintain tolerances, but HKAU offered a more simple solution on the basis that such an automated system would still be subject to the inaccuracies of the tunnel construction and the rolling gantry. The automated system also appeared to be prohibitively expensive. Thus the agreed solution included a rigid system with several manual controls, complimented with some automation to assist with the production objectives.

The automation solution was limited to hole depth control, reinforcement detection and an auto-cycle capability. These functions were controlled by an on board PLC located in the operator control box. The reed switches on the drill stroke cylinder were provided for hole depth control. These switches could be manually adjusted along the cylinder body to set an accurate hole depth. The same sensors were used for reinforcement detection by only allowing the drill a fixed amount of time to advance from the retracted position to the required hole depth. If the hole depth was not achieved in the fixed time the drill was retracted automatically and the drill rig stopped. The auto-cycle function allowed the operator to initiate one drilling operation while setting up the next drill.

A pneumatic system was used for extending the drill feed and for actuating the drill stroke. The design intention was to provide sufficient bracing and drilling forces, while also allowing cushioning of the drill bit in the event of striking reinforcement.




Figure 7 - CADs GA drawing



Figure 8 - CADS basic elements

- |                         |                          |
|-------------------------|--------------------------|
| 1. Rear drilling rig    | 5. Right-side rear rail  |
| 2. Front drilling rig   | 6. Right-side front rail |
| 3. Left-side front rail | 7. Cable/hose reel unit  |
| 4. Left-side rear rail  | 8. Control panel         |

General Data	
Description	Eight independent electric/pneumatic drilling rig units per tunnel in top and bottom configurations
Power supply	Diesel generator provided by TJV, cable reel to each rig provided by HKAU
Air supply	Air compressor provided by TJV, hose reel to each rig provided by HKAU
Control	PLC programmed functions, rig-mounted control box, auto-cycle function
Weight: Front drill rig	164 [kg]
Weight: Rear drill rig	175 [kg]
Weight: Rail	620 [kg]
Longitudinal travel	
Rails and bearings	35 [mm] linear rail with ball-bearing guide blocks
Travel actuation	Manual movement only available after activation of manual brake release pedal
Range	4 [m] travel per rig, mechanical end stops
Height adjustment	
Manual adjustment	HKAU innovative incremental raise system, 600 [mm] total adjustment
Operational adjustment	Electric, ball-screw type linear actuator, driving a parallel linkage mechanism

<b>Feed extension</b>	
Actuation	32 [mm] bore, 600 [mm] stroke pneumatic cylinder
Rails and bearings	35 [mm] linear rail with ball-bearing guide blocks
<b>Drill stroke</b>	
Actuation	32 [mm] bore, 400 [mm] stroke pneumatic cylinder
Rails and bearings	35 [mm] linear rail with ball-bearing guide blocks
<b>Dustless drill system</b>	
Drill	Hilti TE70 electric hammer drill
Drill bit	Ø25 [mm] tungsten carbide tipped hollow drill bit with vacuum attachment
Vacuum	Hilti vacuum

Table 2 – CADS technical specification

#### 5.4. Operation, problems & solutions

CADS operation began in late October 2013 with one crew of up to 6 operators per shift per gantry. From the start of drilling production the hole positions were not accurately marked out, and instead the operators were provided a painted target approximately 100 mm square (refer *Figure 10*). Uncertain of the location of the reinforcement in the segments the operators had a very high rate of reo strikes, with more than a dozen attempts at one hole location before successfully avoiding steel. The decision to opt for simplicity over automated distance measuring was immediately validated. As the operators became more familiar with the production process the production rate increased and reo strikes decreased. The initial production objective of 480 holes per shift was realised, and the best average cycle time achieved was around 1.5 minutes per hole. The number of personnel was slowly reduced over the project until only 3 operators per crew per shift were used to achieve the required production rate. In April 2014 the 102,000 anchors holes were complete.

The low point sump did not present a great problem, with the inbuilt manual height adjustment adequately allowing for the elevation change. The changed hole mark out methodology and the frequency of reo strikes made it necessary to drill some holes outside the original design range. In some cases these holes could still be drilled with the CADS, and in other cases the drills were temporarily dismantled and used manually.

The pneumatic system was very effective for the drilling, but the drill extension cylinder did at times lack enough force to brace the rig. Fortunately the drilling of the hole was unaffected and holes would remain true. No modification was made during operation.

The control boxes were initially mounted too low for ergonomic operation. TJV modified the control box height to improve this issue, and later the operators themselves added seats to the rig for their own comfort. The PLC control worked effectively but was arguably unnecessary since hole depth could potentially be controlled manually.

The system did not require significant maintenance, but the CADS units were kept functional by TJV. The Hilti dustless system effectively eliminated the potential for moving parts to block up with concrete dust. No noticeable wear or fatigue was encountered, and all of the 16 units maintained high availability for the project duration.





Figure 10 – CADS Production phase, reinforcement strikes

## 5.5. Evaluation


Mechanically the system proved reliable, however the adjustment of the drilling angle needed to be improved to simplify this function. The linear rails and guide blocks, normally used in precision machines, were highly successful and required very little maintenance.

The dustless drill system contributed greatly to the CADS success. Smooth operation of the mechanical parts would have been greatly reduced had concrete dust been an issue in the working environment.

The CADS electric system performed satisfactorily. The hole depth control was accurate to within 5 mm, and the auto-cycle effectively allowed the operators to control multiple rigs simultaneously. Drill retraction after labouring on reinforcement was valuable for maximising drill bit life.

Future improvements would see easier angular adjustment, and an increase in the drill feed extension cylinder bore diameter to ensure firm bracing. The use of PLC control and auto-cycling would need to be assessed for its benefit. The control box position required more considered ergonomic design.

As a prototype system the CADS performed above expectations and completed the project on time and without major problems. Off the back of the success of the CADS, two separate, non-PLC controlled rigs were later ordered by TJV for drilling the jet fan hanger brackets above the smoke duct. These new rigs had simple pneumatic controls, and also completed their task satisfactorily and without operational issues (refer Figure 11).



*Figure 11 – Jet fan hanger bracket drilling rig (pneumatic control)*

## **6. Summary**

The SDES and CADs projects were deemed successful by TJV and HKAU, with both parties satisfied with the performance and reliability of the prototype machines. The collaborative development of two innovative new systems led to mutual success. The problems encountered with the machines were overcome by cooperative efforts. HKAU's design team gained valuable practical experience, and are positioned to improve the foundation designs for future applications.

## **7. Acknowledgments**

The author would like to acknowledge the collaborative efforts of the TJV design and project management teams, especially Tim Brown (Bamser), Ignacio Sanz, Oscar Perez, Antonio Barba, Sergio Garmendia, Jose Sanchez, Daniel Garcia and Daniel Kang.

Acknowledgement is also gratefully extended to Matt Barry, Glenn Kirby and the TJV production and maintenance teams.

Herrenknecht Australia would also like to express appreciation to Martin Cunningham of Hilti, and Eddie McNulty and Kobus Roos of UniSpan for their cooperation in the machine designs.